BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

SCHDULE-B

Name of Work: Improvements to Roads at Navy Layout in Ward No 14

Sl	Description of Work	Unit	Qty	Sanctioned Rates	
				In figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	KSRRB 300-47. Scarifying kankar / gravel / metal crust upto 150mm thick with pick axes and disposal of stuff within a lead of 100 meters including cost of all labour charges Complete as per specifications. MORTH Chapter 3.	**Sqm**	3420.00	**20.25**	**Rupees Twenty & Twenty Five Paise Only**
2	**For Grading I Material** Construction of **granular sub-base** by providing close graded granular sub-base Material, mixing in a mechanical mix plant at OMC, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per Specifications. A. Plant Mix Method.	**Cum**	513.00	**1060.56**	Rupees One thousand and Sixty & Fifty six Paise only
3	Providing, laying, spreading and compacting graded stone aggregate to **wet mix macadam** Specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per Specifications.MORTH Specification No. 406	**Cum**	684.00	**1121.04**	Rupees One thousand One Hundred and twenty One & four paise only
4	Providing and applying **primer coat** with Bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.6 kg / sqm using mechanical means complete as per specifications,	Sqm	3420.00	**44.28**	Rupees Forty four & Twenty eight Paise Only
5	Providing and applaying **bituminous concrete** with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 5.4 to 5.6% of mix and filler, transporting the hot mix to	**Cum**	136.80	11452.32	Rupees Eleven thousand Four hundred fifty two & thirty two Paise Only
6	**Carraige** of Mixed Materials above 15 Km beyound 10Km to 15 Kmslead at		136.80	73.50	RupeesSeventy Three & Fifty Paise Only

EXECUTIVE ENGINEER-2
KRIDL, BBMP DIVISION

Signature of the Contractor

Executive Engineer.

7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	513.00	78.24	Rupees Seventy Eight & Twenty four Paise Only

EXECUTIVE ENGINEER-2
KRIDL, RRMP DIVISION
BANGALORE - 560 010

Signature of the contractor

.Executive engineer